Deer Creek Floodplain Restoration Project:

A Stage O Restoration Case Study in Western Oregon










Kate Meyer, Fisheries Biologist
U.S. Forest Service
Willamette National Forest, Oregon









Historically....


- Depositional alluvial valley (high wood loading/sediment storage)
- Spawning and rearing habitat for ESA-Threatened spring Chinook salmon and foraging habitat for ESA-Threatened bull trout
- Productive habitat for cutthroat and rainbow trout, sculpin, etc.





Land Management History

- Historic riparian logging and stream clean-out reduced channel and floodplain roughness
- 1964 flood scoured entire valley bottom



Land Management History

 Constructed berms channelized the stream...




Land Management History

 ... and created a single-thread, transport channel with minimal floodplain connectivity




Project Goal


Restore lower Deer Creek to a complex, dynamic, depositional alluvial valley




 Identify all berms and artificial features (pink)




 "Reset" valley bottom elevations for full connectivity by redistributing berm material into incised channel (grey)



 Add large wood (green and yellow) throughout the valley bottom to create hydraulic complexity and dissipate energy wherever channels may migrate



- Allow natural processes to create dynamic channels, islands, bars, and complex habitat
- No constructed channels



 200 trees (24-36" dbh) in upland units were pushed over, broken in half, and hauled down to placement sites











 Berms were pushed into incised channel with a dozer and excavator

 450 pieces of large wood were placed in jams and single pieces throughout the valley bottom







25 streamside trees
 (38-63" dbh) were
 pulled over using a
 truck-mounted yarder
 to serve as large, stable
 key pieces







Monitoring Results: Before and After (1yr)

METRIC	BEFORE	AFTER	% INCREASE
LWM Density	•	317 pieces/mile (197 pieces/km)	1500%



Monitoring Results: Before and After (1yr)

METRIC	BEFORE	AFTER
Median Particle Size of	64-90 mm	45-64 mm
Pool Tailouts	Cobbles	Gravels







Monitoring Results: Before and After (1yr)

METRIC	BEFORE	AFTER
Spring Chinook Salmon	No redds documented	3 redds in
Spawning	since 1993	2017



Valley-wide Sediment Size Class Transects







Wetted Segment Data


- Depth
- Velocity
- Temperature
- Substrate Size

- Geomorphic Feature
- LWM
- Riparian Vegetation



Wetted Segment Data – Depth & Velocity







Wetted Segment Data – Substrate Size



TREATED REACH



Wetted Segment Data – Geomorphic Feature









April 2016 BEFORE

September 2016 IMMEDIATELY AFTER





Berm Removed





April 2016 BEFORE



September 2016 IMMEDIATELY AFTER



September 2017 ONE YEAR AFTER






























Lessons Learned and Applied to Next Project

- 1. Project objectives and monitoring plan need to be related to indicators of restored processes, such as:
 - sediment storage
 - channel migration/avulsion
 - diversity of geomorphic features
 - water table height
 - wetted area
 - diversity of substrate and velocity
 - amount of cold water refugia
- 2. Need to have more biological monitoring metrics like abundance, composition and distribution of species (fish, macros, amphibians, birds)
- 3. TRUST IN THE FORCE AND BE FEARLESS



Acknowledgements

Project Core Team

- Jared Weybright, Executive Director, McKenzie Watershed Council (Project Co-manager)
- Johan Hogervorst, Hydrologist, Willamette National Forest
- Paul Powers, Fisheries Biologist, Deschutes National Forest
- Mickey Means-Brous, Fisheries Trainee, Willamette National Forest
- Jennifer Weber, Projects Coordinator, McKenzie Watershed Council
- Nick Grant, Hydrologist, Willamette National Forest
- Stephanie Bianco, OSU Graduate Student

Project Funders

- Oregon Watershed Enhancement Board
- National Fish and Wildlife Foundation, Bring Back the Natives Program
- Payments to Counties/Title II Funding (US Forest Service)
- Western Native Trout Initiative/US Fish and Wildlife Service

Contractors

- Haley Construction Company, Inc.
- Blue Ridge Timber Cutting







